

AD-A072 234

O'BRIEN AND GERE ENGINEERS INC PHILADELPHIA PA JUSTIN--ETC F/G 13/2
NATIONAL DAM INSPECTION PROGRAM. LOWER LAKE DAM (NDI-PA 00306, --ETC(U)
MAY 79
DACW31-79-C-0010

UNCLASSIFIED

NL

1 OF 1
AD
A072234





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

DELAWARE RIVER BASIN
EAST BRANCH WALLENPAUPACK CREEK, PIKE COUNTY

PENNSYLVANIA

LOWER LAKE DAM


NDI - PA 00306

PA DER 52-144

LEVEL *TA*

PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM

ORIGINAL CONTAINS COLOR PLATES: ALL DDC
REPRODUCTIONS WILL BE IN BLACK AND WHITE




Distribution Unlimited
Approved for Public Release *OK*
Contract No. DACW31-79-C-0010

DDC FILE COPY.



Prepared By
O'BRIEN & GERE

Justin & Courtney Division
PHILADELPHIA, PENNSYLVANIA
19103



FOR
DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT CORPS OF ENGINEERS
BALTIMORE, MARYLAND
21203

MAY 1979

79 08 06 055

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

12 94p.

11 May 79

DELAWARE RIVER BASIN

Name of Dam: Lower Lake Dam

County and State: Pike County, Pennsylvania

Inventory Number: PA 00306

15 DACW 31-79-C-0010

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

6 National Dam Inspection Program.
Lower Lake Dam (NDI-PA 00306, PA
DER 52-144), Delaware River Basin,
East Branch Wallenpaupack Creek, Pike
County, Pennsylvania. Phase I Inspection Report.

Prepared by:

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION

For:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By _____	
Distribution/	
Availability Codes	
Dist.	Avail and/or special
A	23

410760 Gen

79 08 06 055

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAMS

Name of Dam:	Lower Lake Dam	ID # PA 00306
State Located:	Pennsylvania	
County Located:	Pike	
Stream:	East Branch Waullepaupack Creek	
Coordinates:	Latitude 41° 19.1', Longitude 75° 12.6'	
Date of Inspection:	December 6, 1978	

ASSESSMENT

Lower Lake Dam is an earth embankment with a concrete gravity spillway. The embankment is approximately 340 feet in length with a maximum height of 22.5 feet. The spillway is a broad crested weir, 140 feet in length, divided into three sections. The reservoir drain system consists of two 72" x 44" corrugated metal pipes controlled by means of 36-inch diameter sluice gates. The dam impounds a 250 acre reservoir for recreation within the Promised Land State Park.

Examination of the results of the hydrologic and hydraulic analyses indicates that the spillway is capable of passing the 0.5 PMF, therefore, the spillway is classified as adequate.

Based on visual observations made on the date of the inspection, the dam and its appurtenant structures are considered to be in good condition. Riprap on the upstream side of the embankment is missing or covered by grass and earth. Minor settlement has occurred in an area adjacent to the downstream side of the right wingwall. A crack and movement of the left wingwall at the tie-in with the upstream slope of the embankment has occurred. Erosion has created depressions on the upstream side of the embankment, particularly the lower half of the right side of the embankment and along both wingwalls.

Recommendations and remedial measures are as follows:

a. Facilities

1. Eroded areas on the upstream face of the embankment should be filled; graded filter and riprap should be provided where wave protection is inadequate.
2. The area of settlement adjacent to the right wingwall on the downstream side should be excavated several feet and the backfill

material compacted. Monthly observations should be made to check for settlement.

3. The crack in the upstream side of the left wingwall and the adjacent construction joint should be monitored for further movement.

b. Operation and Maintenance Procedures

1. A warning system should be developed. During periods of heavy rainfall or rapid snowmelt, the dam should be monitored and downstream residents alerted in the event of an impending failure.

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION

Will M. Heiser


Will M. Heiser, P.E.
Vice-President
Pennsylvania Registration #006926-E



June 8, 1979

James W. Peck
Approved By
JAMES W. PECK
Colonel, Corps of Engineers
District Engineer

Date: *16 JUL 1979*



*OVERVIEW
LOWER LAKE DAM, PIKE COUNTY, PENNSYLVANIA*

TABLE OF CONTENTS

	<u>PAGE</u>
SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	3
SECTION 2 - ENGINEERING DATA	
2.1 Design	5
2.2 Construction	5
2.3 Operation	5
2.4 Evaluation	6
SECTION 3 - VISUAL INSPECTION	
3.1 Findings	7
SECTION 4 - OPERATIONAL FEATURES	
4.1 Procedures	8
4.2 Maintenance of the Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning System in Effect	8
4.5 Evaluation of Operational Adequacy	8
SECTION 5 - HYDRAULICS AND HYDROLOGY	
5.1 Evaluation of Features	9
SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	10
SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND PROPOSED REMEDIAL MEASURES	
7.1 Dam Assessment	11
7.2 Recommendations and Proposed Remedial Measures	11

TABLE OF CONTENTS
(Continued)

APPENDIX A -	CHECKLIST, ENGINEERING DATA, DESIGN
	CONSTRUCTION, OPERATION, PHASE I
APPENDIX B -	CHECKLIST, VISUAL INSPECTION, PHASE I
APPENDIX C -	HYDROLOGIC & HYDRAULIC DATA
APPENDIX D -	PHOTOGRAPHS
APPENDIX E -	DRAWINGS
APPENDIX F -	SITE GEOLOGY

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LOWER LAKE DAM
NDI ID NO. PA-00306
DER # 52-144

SECTION 1

PROJECT INFORMATION

1.1 General

- a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.
- b. Purpose of Inspection. The purpose of this inspection is to evaluate the structural and hydraulic conditions of the Lower Lake Dam and appurtenant structures, and to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project

- a. Dam and Appurtenances. (Supplemented by information obtained from the Pennsylvania Department of Environmental Resources (DER), Division of Dam Safety.)

Lower Lake Dam is an earth embankment with a concrete gravity spillway. The embankment is approximately 340 feet in length with a maximum height of 22.5 feet. The dam impounds a reservoir with a surface area of 250 acres and a storage capacity of 1,085 acre-feet at normal pool level. The top of the dam is 20 feet wide; the upstream and downstream side slopes are approximately 2.5 horizontal to 1.0 vertical (2.5H:1V). No information is available concerning the properties of the embankment materials. Within the embankment is a tapered reinforced concrete cutoff wall that extends from bedrock to 3.5 feet below the top of the embankment.

The reinforced concrete spillway, which has a maximum height of 13 feet from base to crest, consists of 3 sections separated by bridge piers. Each section is a broad-crested weir with a vertical upstream face and a flat, sloping downstream face. The crest of the center section is 48.5 feet long and the crest of each of the two end sections is 45.75 feet long. The crest of the center section, which is 3 feet wide, is 0.5 feet below the crest of the end sections; each of the end sections is 2.5 feet wide. At the base of the weir is a stilling basin with baffle blocks. The stilling basin slab, which has six 3-inch weep holes, overlays a 6-inch layer of

stone. Approximately 26 feet downstream of the toe of the spillway is a 2 foot high weir or end sill with six 3"x6" semicircular drains. The stilling basin floor extends an additional 3 feet downstream from the toe of the end sill. This additional section is cantilevered above an apron located 4 feet below the overhang. Seven 4-inch pipes pass through the end wall supporting the stilling basin slab to provide drainage for the 6-inch layer of stone that is under the stilling basin slab.

The reservoir drain system consists of two 72"x44" corrugated metal pipes located near the base of the two bridge piers. Flow through the pipes discharges on the apron. The flow is controlled by means of 36 inch diameter sluice gates located at the upstream end of the pipes. The sluice gates are operated from the bridge deck.

The underside of the concrete bridge structure is located approximately 7 feet above the crest of the spillway and has an 18-foot wide asphalt roadway.

- b. Location. Lower Lake Dam is located on the East Branch of Waullen-paupack Creek at a point about 1 mile west of Promised Land, in Green Township, Pike County, Pennsylvania. The dam site is shown on the USGS Quadrangle entitled "Promised Land, Pennsylvania" at coordinates N 41° 19.1', W 75° 12.6'. A regional location plan of Lower Lake Dam is included as Plate 1, Appendix E.
- c. Size Classification. Lower Lake Dam has a maximum capacity of 1,347 million gallons (4,140 acre-feet) and a maximum height of 22.5 feet. The structure is in the intermediate size category.
- d. Hazard Classification. There are approximately 40 private residences on Lake Paupack, which is located 1.5 miles downstream of Lower Lake Dam. The topography downstream of the dam is such that flood waters would not be directed toward these homes. Therefore, the structure is in the "Significant" hazard category.
- e. Ownership. The dam is owned and operated by the Commonwealth of Pennsylvania, Department of Environmental Resources. Correspondence should be addressed to the Commonwealth of Pennsylvania, Department of Environmental Resources, P.O. Box 1467, Harrisburg, Pennsylvania, 17120.
- f. Purpose of the Dam. The dam was built to provide a reservoir for recreation in the Promised Land State Park.
- g. Design and Construction History. The dam was designed by L. Robert Kimball, a consulting engineer, and was constructed by the Pocono Mountains Construction Company, Inc. between 1958 and 1959. Repairs to the abutment wingwalls to correct structural deficiencies and drainage problems were made in 1963 and 1964.

- h. Normal Operating Procedures. According to the Park Foreman, the lake is normally maintained at Elevation 1707.0 which is the elevation of the center spillway crest. Operating procedures are limited to the operation of the two sluice gates, which are normally in a partially open position. A minimum release of 1.6 cfs. is required by DER.

1.3 Pertinent Data

a. Drainage Area.

Square Miles	10.6
--------------	------

b. Discharge at Dam Site (cfs.).

Total Spillway Capacity at top of dam Elev. 1717.0	14,620
---	--------

c. Elevation (Feet above MSL).

Spillway Crest, Center Section (Normal, Recreation Pool)	1707.0
Spillway Crest, Outer Sections	1707.5
Top of Dam (at low point of top of dam)	1717.0
Reservoir Drain Invert	1694.5
Streambed at Centerline of Dam	1694.5

d. Reservoir (Miles).

Length of Normal, Recreation Pool	1.2
Length at Maximum Non-overtopping Pool	1.4
Fetch at Normal Pool	0.5

e. Storage (acre-foot).

Normal, recreation pool, Elev. 1707.0	1,085
Top of Dam at Low Point, Elev. 1717.0	4,140

f. Reservoir Surface Area (acres).

Normal, Recreation Pool, Elev. 1707.0	250
Top of Dam at Low Point, Elev. 1717.0	365

g. Dam Data.

Type	Earth
Length	340 feet
Height	22.5 feet (maximum)
Top Width	20 feet
Side Slopes	2.5H:1V (upstream and downstream)
Zoning	No
Impervious Core	No
Cutoff	Yes
Grout Curtain	No

h. Spillway.

Type	Broad-crested weir
Length	48.5 feet (center sections) 45.75 feet (outer sections)
Width	3.0 feet (center section) 2.5 feet (outer sections)
Crest Elevation	1707.0 (center section) 1707.5 (outer sections)
Gates	None
Upstream Channel	Lower Lake
Downstream Channel	Follows a natural draw through a heavily wooded region.

i. Outlet Works.

Type	Two 72"x44" CMP's
Length	50 feet
Closure	Two 36-inch diameter sluice gates at upstream end.
Access	Intake is submerged; Hand- operated mechanism for sluice gate on deck of bridge.
Regulating Facilities	Hand operated sluice gates

SECTION 2

ENGINEERING DATA

2.1 Design

- a. Data Available. The information available for review of Lower Lake Dam includes the following (all information obtained from the Pennsylvania DER main office files in Harrisburg, Pennsylvania):
1. Dam inspection reports beginning in 1962 and through the intervening years.
 2. Photographs beginning in 1958 and through the intervening years.
 3. Application, Report Upon the Application and Permit for construction of Lower Lake Dam.
 4. Seven design drawings - L. Robert Kimball, consulting Engineer.
 5. Miscellaneous correspondence.
- b. Design Features. The design features are discussed in Section 1.2.a and shown on Plates 2, 3, 4 and 5 of Appendix E.

2.2 Construction

The construction data available in the Pennsylvania DER offices in Harrisburg, Pennsylvania, are several photographs, construction reports and correspondence. The dam was constructed by the Pocono Mountains Construction Company, Inc. between 1958 and 1959. Repairs to the downstream wingwalls were made in 1963 or 1964 to correct structural deficiencies. Saturated earth loads on the wingwalls had caused deflections of the walls, openings in joints, and fracturing in the south abutment wingwall. The repairs to the wingwalls were made, additional weepholes were drilled in the walls, and a drainage system constructed to carry the runoff below the wingwalls.

2.3 Operation

Operation procedures appear to be limited to those necessary to maintain a minimum flow of 1.6 cfs. or to draw the lake down by means of the sluice gates, which are operated from the bridge deck. There is no evidence that operating procedures have been written for this structure.

2.4 Evaluation

- a. Availability. All information made available was obtained from DER.
- b. Adequacy. Information supplied by DER, observations made during the field inspection, and discussions with the park foreman provided sufficient material to perform a Phase I evaluation.
- c. Validity. There appears to be no reason to question the validity of the information available.

SECTION 3

VISUAL INSPECTION

3.1 Findings

- a. General. The field inspection of the Lower Lake Dam took place on December 6, 1978. The reservoir water surface elevation was approximately an inch above the spillway crest of the center section during the inspection. No underwater areas were inspected. The observations and comments of the field inspection team are in the checklist which is Appendix B of this report. The appearance of the facility indicates that the dam and its appurtenances are well maintained.
- b. Dam. The riprap on the upstream side of the embankment is missing or covered by grass and earth. There is an area of minor settlement of up to 3 inches in the embankment adjacent to the downstream right wingwall tie-in. This area is approximately 3 feet wide and 30 feet long. Erosion has created depressions up to 12 inches deep along both upstream wingwalls and depressions up to 3 inches deep on the lower half of the upstream slope on the right side of the embankment. The depressions along the wingwalls cover a 2 to 3 feet wide strip from the top of the dam to the waterline. The eroded area of the embankment covers a 7 foot wide strip starting at the wingwall and extending approximately 40 feet.
- c. Appurtenant Structures. A crack at the upstream end of the left wingwall at the tie-in was observed as well as a differential movement of approximately 1/4 inch of an adjacent construction joint. Occasional hairline cracking and spalling of the wingwalls were noted.

The park foreman, Carl Rose, opened both sluice gates further to demonstrate that they were fully operational.
- d. Reservoir. Area reconnaissance of the reservoir disclosed no evidence of excessive siltation, slope instability, or other features that would significantly affect the storage capacity of the reservoir. The slopes along the perimeter are heavily vegetated and on gradients of less than 15 percent. Promised Land Dam is located immediately upstream of the reservoir.
- e. Downstream Channel. Below Lower Lake Dam, the East Branch of Waullenpaupack Creek flows through heavily wooded areas for 1.5 miles before reaching Lake Paupack. The channel gradient averages about 1.1% for this section of the creek.

SECTION 4

OPERATIONAL PROCEDURES

4.1 Procedures

Operational procedures have been covered in section 1.2.h. According to the owner's representative, written operating procedures are not available. Normal operating procedures for this structure do not require a dam tender.

4.2 Maintenance of the Dam

The dam appears to be well maintained by the Promised Land State Park personnel. Maintenance inspections are reported to be conducted on a regular basis by both the Park Superintendent and personnel from the Division of Completed Projects, DER. Records and photographs of these inspections are available. Regular maintenance performed has consisted of minor concrete repairs and debris removal.

4.3 Maintenance of Operating Facilities

According to the maintenance records, the sluice gates are checked, lubricated, and operated on a regular basis by Promised Land State Park personnel.

4.4 Warning System in Effect

According to the Park Superintendent, no formal warning systems or procedures have been established for periods of high lake levels.

4.5 Evaluation of Operational Adequacy

The current operating and maintenance procedures for the Lower Lake Dam appear to be adequate, even though there are no formal operating procedures.

A warning system should be developed. During periods of heavy rainfall or rapid snowmelt, the dam should be monitored and downstream residents alerted in the event of an impending failure.

The dam is accessible under all weather conditions for inspection and emergency action.

SECTION 5

HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features

- a. Design Data. No original design data is available. The drainage area contributing to Lower Lake Dam is about 5.0 miles long and averages about 2.1 miles wide. Ground elevations range from 2012 to 1707. The slopes of the watershed adjacent to the reservoir are all less than 15 percent. The watershed is nearly 100 percent wooded.

For further information, refer to the computations, data, and printouts included in Appendix C.

- b. Experience Data. According to the owner's representative, no regular records of reservoir water levels are maintained. However, during Hurricane Agnes in June, 1972, the stage in the reservoir was observed to be 18 inches above the crest of the spillway. Rainfall records for Promised Land State Park are maintained at the Park Office.

- c. Visual Observations. On the date of the inspection, no adverse conditions were observed that would indicate that the spillway capacity would be reduced during a flood. Further observations are given in Appendix B.

- d. Overtopping Potential. The spillway is capable of handling a discharge of 11,700 cfs. The SDF for this "Intermediate" size dam, with a "Significant" hazard classification, is the 0.5 PMF which has a peak inflow of 4,570 cfs. and a peak outflow of 3,190 cfs. The 0.5 PMF hydrograph for the Promised Land Dam drainage area was routed through that reservoir with a starting water surface elevation at 1726.3, 0.2 above the crest of the spillway, and into Lower Lake. At this point, the routed Promised Land Dam hydrograph was combined with the 0.5 PMF hydrograph for the Lower Lake drainage area and routed through Lower Lake with a starting water surface elevation of 1707.3, 0.3 feet above the crest of the center section of the spillway. The maximum water surface elevation in the Lower Lake Reservoir resulting from this routing is 4.0 feet above the spillway crest of the center section and 6.0 feet below the lowest point of the top of the dam.

Examination of the results of the hydrologic and hydraulic analyses indicates that the spillway is capable of passing the 0.5 PMF without overtopping the embankment (See Appendix C for computations).

- e. Spillway Adequacy. The Lower Lake Dam spillway is classified as adequate.

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

- a. Visual Observations. Riprap facing on the upstream slope of the embankment is missing or covered by grass and earth. Minor settlement of up to 3 inches of the embankment adjacent to the downstream right wingwall tie-in could be due to poor compaction of earth adjacent to wingwall.

A crack at the upstream end of the left wingwall at the tie-in and movement of an adjacent construction joint of approximately 1/4 inch were observed. However, this should have minor effect on the overall stability of the structure. Occasional hairline cracking and spalling of the wingwalls were noted.

Based on the available information and field observations, the embankment and spillway appear to be in good condition with no visible signs of structural instability.

- b. Design and Construction Data. A partial set of design drawings is available. No design calculations or soil data are available. Lists of the design and construction data reviewed are given in Section 2.1.a and 2.2.
- c. Operating Records. There is no evidence that operating records are maintained for the Lower Lake Dam.
- d. Post-Construction Changes. The available information indicates that the only major modifications to the original structure were made in 1963 or 1964 on the wingwalls to correct deflections of the walls, openings in joints, and fracturing of concrete in the south abutment wingwall. The wingwalls were repaired, additional weepholes drilled in the walls, and a drainage system constructed to carry the runoff below the wingwalls. Information is available in the DER files on maintenance work done on the dam through the years.
- e. Seismic Stability. Lower Lake Dam is located within Seismic Risk Zone 1 of the "Seismic Zone Map of Contiguous States". Normally, it can be considered that if a dam in this zone is stable under static loading conditions, it can be assumed safe for any expected Zone 1 earthquake conditions.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment

- a. Evaluation. Based on visual observations made on the date of the inspection, the dam and its appurtenant structures are considered to be in good condition. Riprap on the upstream side of the embankment is missing or covered by grass and earth. Minor settlement has occurred in an area adjacent to the downstream side of the right wingwall. A crack and movement of the left wingwall at the tie-in with the upstream slope of the embankment has occurred. Erosion has created depressions on the upstream side of the embankment, particularly the lower half of the right side of the embankment and along both wingwalls.

The SDF is the 0.5 PMF. Examination of the results of the hydrologic and hydraulic analysis indicates that the spillway is capable of passing the 0.5 PMF and, therefore, is adequate.

- b. Adequacy of Information. A Phase I evaluation is considered reasonable based on observations made during the field inspection, information supplied by DER, and conversations with the owner's representative.
- c. Urgency. The remedial measures recommended in Section 7.2 should be effected as soon as possible.
- d. Necessity for Further Evaluation. No further investigations are recommended at this time.

7.2 Recommendations and Proposed Remedial Measures

a. Facilities

1. Eroded areas on the upstream face of the embankment should be filled; graded filter and riprap should be provided where wave protection is inadequate.
2. The area of settlement adjacent to the right wingwall on the downstream side should be excavated several feet and the backfill material compacted. Monthly observations should be made to check for settlement.
3. The crack in the upstream side of the left wingwall and the adjacent construction joint should be monitored for further movement.

b. Operation and Maintenance Procedures

1. A warning system should be developed. During periods of heavy rainfall or rapid snowmelt, the dam should be monitored and downstream residents alerted in the event of an impending failure.

APPENDIX

A

Check List Engineering Data
Design, Construction, Operation
Phase I

APPENDIX

A

Check List Engineering Data
Design, Construction, Operation
Phase I

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM Lower Lake Dam
ID # PA - 00306

Sheet 1 of 4

REMARKS

There are no "As-Built" drawings available. There are 7 Design drawings in DEIR file. See Plates 2, 3, 4, and 5 in Appendix E.

Refer to Appendix E, Plate 1

The dam was built in 1958-1959 by the General State Authority of Pennsylvania for the purpose of creating a recreation pool. The structure was designed by L. Robert Kimball, P.E. & constructed by Pocono Mountain Construction Co., Inc.. Repairs to the abutment wingwalls to correct fracture and drainage problem were made in 1961 and 1962.
Refer to Plates 2, 3, 4, and 5 in Appendix E.

Refer to Plate 2, Appendix E. 72" x 44" CMP pipes controlled by 36" diameter sluice gates.

Not available.

Rainfall records available at Promised Land State Park office.

REMARKS

ITEM

DESIGN REPORTS "Report Upon The Application of the Department of Forests and Waters" for Lower Laka Dam available in DER files.

GEOLOGY REPORTS None provided in DER files. Refer to Appendix F of this report

DESIGN COMPUTATIONS NO data available
HYDROLOGY & HYDRAULICS NO data available
DAM STABILITY NO data available
SEEPAGE STUDIES NO data available

MATERIALS INVESTIGATIONS

BORING RECORDS }
LABORATORY }
FIELD }
Brief descriptions of boring logs and excavation in "Report Upon the Application of the Department of Forests and Waters" for Lower Laka Dam and in construction reports.

POST-CONSTRUCTION SURVEYS OF DAM May, 1961 inspection of dam by G.S.A. engineer

BORROW SOURCES There is no record of the source of the borrow material.

ITEM	REMARKS
------	---------

MONITORING SYSTEMS

None

MODIFICATIONS

Additional weep holes added to downstream retaining walls.

HIGH POOL RECORDS

June, 1972 - Hurricane Agnes - 18 inches of water on top of weir

POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS

None

PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS

Fracturing, deflection, and separation of retaining walls on downstream side - noted May, 1961 - repaired walls and weep holes added.

MAINTENANCE OPERATION RECORDS

Regular maintenance inspections from June, 1962 to present date. Maintenance performed noted in reports. Information available in DER files.

ITEM	REMARKS
SPILLWAY PLAN	Refer to Appendix E
SECTIONS	
DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	No information available.
MISCELLANEOUS	<p>Material in DER files:</p> <ol style="list-style-type: none"> 1. Engineering Drawings 2. Construction Reports 3. Dam inspection reports through the years. 4. Photographs taken during dam inspections. 5. Miscellaneous correspondence. 6. Application, Report upon the Application, and Permit for Construction of Lower Lake Dam

APPENDIX

B

Check List
Visual Inspection
Phase I

CHECK LIST
VISUAL INSPECTION
PHASE I

Sheet 1 of 11

Name Dam Lower Lake Dam County Pike State Pennsylvania National ID # PA-00306
Type of Dam Earth Fill/Conc. Gravity Hazard Category High
Date(s) Inspection Dec. 6, 1978 Weather clear, cold Temperature -32°

Pool Elevation at Time of Inspection 1707.1 M.S.L. Tailwater at Time of Inspection 1694 M.S.L.

Inspection Personnel:

George C. Elias Dana R. Pizarro
David B. Campbell
Thomas C. Ahn
David B. Campbell Recorder

Remarks:

Carl Rose, Promised to do State Park foreman, accompanied inspection
personnel.

CONCRETE/MASONRY DAMS

Sheet 2 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

ANY NOTICEABLE SEEPAGE

None Observed

STRUCTURE TO
ABUTMENT/EMBANKMENT
JUNCTIONS

No separation observed

DRAINS

Drains for 6" stone layer
under stilling basin slab
are working. Weep holes in
stilling basin slab drain into
6" stone layer

WATER PASSAGES

N/A

FOUNDATION

Not Observed

CONCRETE/MASONRY DAMS

Sheet 3 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Occasional hairline cracking of wing walls, some minor spalling.	Patch cracks & spalls
STRUCTURAL CRACKING	Slight cracking at upstream end on left wing wall at tie-in.	Continue to observe, no problem noted.
VERTICAL AND HORIZONTAL ALIGNMENT	No alignment problems observed.	-
MONOLITH JOINTS	No problems observed	-
CONSTRUCTION JOINTS	Small differential movement of construction joint on upstream side of left wing wall separation between left end of weir wall and south wing wall	Continue to observe

EMBANKMENT

Sheet 4 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None observed	—
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed	—
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Erosion along upstream side of left wingwall. Erioxon has created depression about 1.5' deep along upstream side of right wingwall. General erosion of lower half of upstream slope on right side.	Fill eroded areas and reseed
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	No misalignment observed	—
RIPRAP FAILURES	Upstream slope supposed to have 2 foot thick riprap layer. Riprap is missing or under grass and earth.	Restore riprap facing of upstream slope.

EMBANKMENT

Sheet 5 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
DRAINS	Weep holes on both wing walls drain portion of embankment, weep holes are discolored, some discharging water (exp to outlet)	—
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Some minor settlement adjacent to right wing wall tie-in. Both upstream and downstream	—
ANY NOTICEABLE SEEPAGE	None observed	—
STAFF GAGE AND RECORDER	None	—

OUTLET WORKS

Sheet 6 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	N/A	-
INTAKE STRUCTURE	Not observed, under water Park foreman opened both sluice gates	-
OUTLET STRUCTURE	72" x 44" CMP, couldn't observe interior (CMP controlled by 36" diam. sluice gates)	-
OUTLET CHANNEL	CMP's empty onto concrete apron, then to natural channel which enters heavy woods about 500 feet away	-
EMERGENCY GATE	2 - 36" diam sluice gates controlling 2 - 72" x 44" CMP's	-
BRIDGE	Steel bridge with 2 - 1'-6" piers (conc.) on spillway, bridge 7'-3" above center section of spillway, bridge has asphalt roadway.	-

UNIGATED SPILLWAY

Sheet 7 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	breast-cracked weirs (2'-6" wide), 3 sections, crest elevation of outer sections about 6" higher than center section, weir has vertical upstream face and flat sloping downstream face	-
APPROACH CHANNEL	lower lake	-
DISCHARGE CHANNEL	water flows over weir into stilling basin with baffle blocks, water from stilling basin discharged through and over end sill (weir wall) and drops to concrete apron, then to natural channel	-
BRIDGE AND PIERS	See sheet 6/11	

GATED SPILLWAY

Sheet 8 of 11

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

CONCRETE SILL

N/A

APPROACH CHANNEL

N/A

DISCHARGE CHANNEL

N/A

BRIDGE AND PIERS

N/A

GATES AND OPERATION
EQUIPMENT

N/A

INSTRUMENTATION

Sheet 9 of 11

<u>VISUAL EXAMINATION</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
---------------------------	---------------------	-----------------------------------

MONUMENTATION/SURVEYS

None

OBSERVATION WELLS

None

WEIRS

None

PIEZOMETERS

None

OTHER

N/A

RESERVOIR

Sheet 10 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

All slopes less than 15%,
shoreline generally heavily
wooded, park facility areas
are partially cleared

SEDIMENTATION

None observed

DOWNSTREAM CHANNEL

Sheet 11 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

CONDITION
(OBSTRUCTIONS,
DEBRIS, ETC.)

Channel flows through heavily wooded areas for 1.5 miles to Lake Paupack. No bridges or man-made obstructions.

SLOPES

The channel gradient averages about 1.1% for the 1.5 miles from lower Lake Dam to Lake Paupack.

APPROXIMATE NO.
OF HOMES AND
POPULATION

There are approximately 40 homes on Lake Paupack with an estimated population of 200.

A formal warning system should be developed and implemented. Procedures for evacuating people within the potential flood area should be implemented.

APPENDIX

C

Hydrologic & Hydraulic Data



TABLE OF CONTENTS APPENDIX C

Hydraulics & Hydrologic Data

Promised Land Dam

Hydrographs, Coefficients & PMP Calculations	Shts. 1 & 2
Stage-Area, Stage-Storage Calculations	Shts. 2, 2a, & 2b
Spillway & Embankment Discharge Comp.	Shts. 3 & 4
Route 370 Culvert Discharge Computations	Shts. 5-9
Channel Routing Below Dam	Sht. 9a

Lower Lake Dam

Hydrographs, Coefficients & PMP Calculations	Shts. 10 & 11
Stage-Area, Stage-Storage Calculations	Shts. 11 & 12
Spillway & Embankment Discharge Computations	Shts. 13-15

HEC-I Dam Safety Version Computer Output	Shts. 19-28
--	-------------

SUBJECT	SHEET	BY	DATE	JOB NO
Copper Promised Land Dam	1	DRP	12/14/75	1841-D10

D.A. = Area I + Area II

$$\text{Area I} = 1.015 \text{ in}^2/\text{unit} \times 27.78 \text{ units} \times 4 \times 10^6 \frac{\text{ft}^2}{\text{in}^2} \times 3.537 \times 10^{-8} \frac{\text{mi}^2}{\text{ft}^2}$$

$$= 4.04 \text{ mi}^2$$

$$\text{Area II} = 1.015 \text{ in}^2/\text{unit} \times 19.53 \text{ units} \times 4 \times 10^6 \frac{\text{ft}^2}{\text{in}^2} \times 3.537 \times 10^{-8} \frac{\text{mi}^2}{\text{ft}^2}$$

$$= 2.84 \text{ mi}^2$$

$$\text{D.A.} = 6.88 \text{ mi}^2 \approx 6.9 \text{ mi}^2 \text{ by planimeter}$$

$$6.57 \text{ mi}^2 \text{ by reports use } 6.57 \text{ mi}^2$$

Hydrograph Parameters (Snyder method)

$$t_p = C_t (L L_c)^{0.3}$$

$$\left. \begin{array}{l} C_t = 1.23 \\ C_p = 0.45 \end{array} \right\} \begin{array}{l} \text{supplied by COE} \\ \text{Zone 1} \end{array}$$

$$L = 4.1 \text{ miles}$$

$$L_c = 1.9 \text{ miles}$$

$$t_p = 1.23 ((4.1)(1.9))^{0.3} = 2.3 \text{ hr.}$$

$$t_r = \frac{2.3 \text{ hr.}}{5.5} = 0.4 \text{ hr.}$$

Probable Maximum Storm (PMS) (Hydromet 33)

Zone 1 (Fig. 1)

$$\text{Probable Max. flood (PMP)} = 22.2 \text{ in. } (200 \text{ mi}^2, 24 \text{ hr})$$

Depth - Area - Duration Relationships

$$\text{Maximum } 6 \text{ hr} = 111\% \text{ PMP}$$

$$\text{Maximum } 12 \text{ hr} = 123\% \text{ PMP}$$

$$\text{Maximum } 24 \text{ hr} = 133\% \text{ PMP}$$

Loss Rate

$$\text{initial loss} = 1''$$

$$\text{uniform loss} = 0.05 \text{ in./hr}$$

Base flow

$$1.5 \text{ cfs/mi}^2 \times 6.57 \text{ mi}^2 = 9.9 \text{ cfs}$$

Elevation - Area - Capacity Data

<u>Elev.</u>	<u>Area (mi²)</u>	<u>Area (acres)</u>
1725.6		422.0 - data
1727	0.72	460.8
1740	1.27	812.8
1760	1.90	1216.0

} planimeter

1720.4

1715.1 (streambed elev.)

287

0

} extension of data
see next page



SUBJECT

PLD

SHEET

2a

BY

DRP

DATE

1/18/79

JOB NO

1841-010

Extend Elevation-Area-Capacity Data below spillway crest
using conic method

$$V = 765,000,000 \text{ gallons at Elev } 1725.6$$

$$A = 422 \text{ acres}$$

$$h = 1725.6 - 1715.1 \text{ (streambed elev)} = 10.5 \text{ ft}$$

$$A = 18,382,320 \text{ ft}^2$$

$$V = 102,272,727 \text{ cf} = 2347 \text{ acre-ft}$$

$$r = \sqrt{A/\pi} = \sqrt{18,382,320 \text{ ft}^2 / \pi} = 2418.9 \text{ ft}$$

$$V = \pi (2418.9)^2 \frac{(10.5)}{3} = 64,335,954 \text{ cf} \quad \text{(single cone)} \\ \text{too low}$$

break into 2 cones

① assume area at $h/2$ is $1/2$ area at h

$$\text{Upper Cone Volume} = \left(\frac{5.25}{3}\right) (422 + 211 + \sqrt{(422)(211)}) \\ = 1629.9 \text{ acre-ft} \approx 71,000,000 \text{ cf}$$

$$\text{Bottom Cone Volume} = \pi r^2 \frac{h}{3} = A \frac{h}{3} = 211 \left(\frac{5.25}{3}\right) = 369.3 \text{ acre-ft} \\ = 16,000,000 \text{ cf}$$

$$\text{Total} = 87,000,000 \text{ cf} \\ \text{too low}$$

② assume area at $h/2$ is 55% area at h

$$\text{Upper Cone Volume} = \left(\frac{5.25}{3}\right) (422 + 232 + \sqrt{(422)(232)}) \\ = 1692 \text{ ac-ft} = 73,700,000 \text{ cf}$$

$$\text{Bottom Cone Volume} = \pi r^2 \frac{h}{3} = (232) \left(\frac{5.25}{3}\right) = 406 \text{ ac-ft} \\ = 17,700,000 \text{ cf}$$

$$\text{Total} = 91,400,000 \text{ too low}$$



SUBJECT

PLD

SHEET

26

BY

DRP

DATE

1/13/79

JOB NO

1841-010

- ③ assume area at $h/2$ is 65% area at h

$$\text{Upper Cone Volume} = \left(\frac{5.25}{3} \right) (422 + 274 + \sqrt{(422)(274)})$$

$$= 1813 \text{ ac-ft} \rightarrow 79,000,000 \text{ cf}$$

$$\text{Bottom Cone Volume} = \left(\frac{5.25}{3} \right) (274) = 479.5 \text{ ac-ft}$$

$$= 20,900,000 \text{ cf}$$

$$\text{Total} = 99,900,000 \text{ cf}$$

- ④ assume area at $h/2$ is 68% area at h

$$\text{Volume} = \left(\frac{5.23}{3} \right) (422 + 2(287) + \sqrt{(422)(287)})$$

$$= 2343 \text{ ac-ft} = 102,064,000 \text{ cf}$$

good

Rev. 4/15/79

Spillway Discharge Rating

$$Q = CLH^{3/2}$$

broadcrested weir (trapezoidal section)

$$B = 14' \text{ (width of weir)}$$

$$C = 3.1 \text{ (Brater \& King)}$$

Reduce L for abutment effects, no piers

$$L = L' - 2(NK_p + K_a)H_e \text{ (Design of Small Dams, 1977)}$$

$$N = 0 \text{ (no piers)}$$

$$K_a = 0.2$$

$$H_e \approx H$$

$$L = 33 - 0.4H$$

$$\text{weir elev} = 1726.1$$

$$\text{embankment elev} = 1731.1$$

$$Q = 3.1 LH^{3/2}$$

<u>H (ft)</u>	<u>L (ft)</u>	<u>Q (cfs)</u>	<u>WSFL</u>
0.7	32.7	59	1726.8
1.5	32.4	185	1727.6
3.0	31.8	512	1729.1
4.5	31.2	923	1730.6
5.0	31.0	1074	1731.1

Embankment Discharge Rating

$$Q = CLH^{3/2}$$

broadcrested weir (trapezoidal)

$$B = 12 + 14' \text{ ft}$$

$$C = 3.1$$

$$\text{Elev } 1731$$

$$L = 140 - 33 = 107' \text{ ft}$$

$$1734.6$$

$$L = 160 - 33 = 127$$

$$1740$$

$$L = 360$$



O'BRIEN & GERE

SUBJECT

Upper Promised Land Dam

SHEET

4

BY

DRP

DATE

12/20/78

JOB NO.

1341-010

4/13/79

<u>Hair</u>	<u>Lair</u>	<u>Quair</u>	<u>Hamb</u>	<u>Lamb</u>	<u>Reimb</u>	<u>Quair + Lamb</u>	<u>Elev.</u>
5	31	1074	0	0	0	1074	1731.1
6.5	31	1593	1.5	116	661	2254	1732.6
8	31	2174	3.0	124	1997	4171	1734.1
9.5	31	2814	4.5	170	5030	7844	1735.6

Rte 390 Bridge

located downstream of dam

could act as a control structure

top of road approx 1733


bottom of culvert approx 1714

semicircular opening

$r = 12'$

crown elev = 1726

Headwater Below Crown (Open Channel flow)



assume critical depth occurs in channel

$d_c = \frac{2}{3}H$

$Q_c = A_c \sqrt{g D_c}$

$A_c = A_1 + A_2$

$A_1 = \frac{\pi r^2}{2} = 574^2$

$A_2 = \frac{2}{3} \left(\sqrt{r^2 - D_c^2} \right) D_c = 514^2$

θ	$D_c (ft)$	$A_c (ft^2)$	$Q_c (cfs)$	Elev*
$22\frac{1}{2}^\circ$	4.6	$57 + 51 = 108$	1314	1720.9
45°	8.5	$113 + 72 = 185$	3061	1726.6
$67\frac{1}{2}^\circ$	11.1	$170 + 51 = 221$	4178	1730.6

centroid = $0.576 R = 6.9$

* $1714 + H = \text{Elev}$

Headwater Above Crown, $H/D < 0.75$

assume well rounded inlet

$C_c = 1, K_i = 0$ (Morris & Wiggert)

$$Q = A \sqrt{2g \left(H + \frac{V_a^2}{2g} \right)}$$

$A = 126.2 \text{ ft}^2$

Assume $\frac{V_a^2}{2g} \approx 0$

H_p	H/D	$Q (cfs)$	Elev
6.9	0.575	4768	1726
7.9	0.67	5102	1727
8.9	0.75	5415	1728

Headwater Above crown, $H/D > 1$

* For $0.75 < H/D < 1$ oscillating heads occur, producing slug flow the curve will be interpolated in this region.

$$Q = A \sqrt{\frac{2g \left(H + \frac{V_0^2}{2g} + S_b L \right)}{1 + f \left(\frac{L}{D} \right)}} \quad R^{4/3} = \left(\frac{\frac{1}{2} \pi R^2}{\pi R + 2r} \right)^{4/3} = 5.65$$

$$f \left(\frac{L}{D} \right) \approx \frac{29.1 n^2 L}{R^{4/3}} = \frac{29.1 (0.025)^2 (36)}{5.65} = 0.12$$

$$\frac{V_0^2}{2g} \approx 0$$

$$S_b L \approx 0$$

$$Q = A \sqrt{\frac{2gH}{1.12}}$$

H_p	H/D	$Q (cfs)$	Elev
11.9	0.99	5916	1731
12.9	> 1	6160	1732
13.9	> 1	6395	1733

When $H_p \geq 13.9$ a combination of weir & pressure flow occurs, see following page for computations

weir length is assumed to be 50' at 1733
 " " " approx. 200 at 1740
 " " " " 800 at 1760



O'BRIEN & GERE

SUBJECT

Upper Atomized Land Dam

SHEET

7

BY

DRP

DATE

12/20/75

JOB NO.

1841-010

Rev 4/13/79

$H_p \geq 13.9$

<u>$H_p (ft)^*$</u>	<u>Pressure Flow</u> <u>$Q_p (cfs)$</u>	<u>$H_w = H_p - 13.9$</u>	<u>L</u>	<u>Q_{weir}</u>	<u>$Q_p + Q_w$</u>	<u>Elev</u>
15.4	6731	1.5	82	467	7198	1734.5
16.9	7051	3.0	114	1836	8887	1736.0

* assumes reservoir level over orifice

Combined Discharge Rating Curve for Route 390 Bridge

<u>Elev.</u>	<u>$Q (cfs)$</u>
1714.0	0
1720.9	1314
1726.0	4768
1727.0	5102
1728.0	5415
1731.0	5916
1732.0	6160
1733.0	6395
1734.5	7198
1736.0	8887

SUBJECT

Upper Promised Land Dam.

SHEET

8

BY

DRP

DATE


1/2/78

JOB NO

1341-010

Rev 2/15/79

RATING CURVE - ROUTE 890
BRIDGE





O'BRIEN & GERE

SUBJECT

Upper Promised Land Dam

SHEET

9

BY


DRP

DATE

5/13/79

JOB NO.

1841-010



Note: Model using dam control only model to 7844 cfs



O'BRIEN & GERE

SUBJECT

Lower Promised Land Dam

SHEET

9a

BY

DEP

DATE


6/5/79

JOB NO

1841-010

Cross-Section at Downstream Residence

Streambed elevation estimated at 1713.7, 100 ft downstream
of Route 3970 Bridge, streambed slope = 0.3%
250 ft downstream of dam



Channel $n = 0.040$
Overbank $n = 0.120$

SUBJECT	SHEET	BY	DATE	JOB NO.
Lower Promised Land Dam	10	DRP	12/14/73	1841-010

$$D.A. = \text{Area I} + \text{Area II} + \text{Area III}$$

$$= 4.04 \text{ mi}^2 + 2.84 \text{ mi}^2 + [1.015 \text{ cu/acre} \times 22.52 \text{ units} \times 4 \times 10^{+6} \frac{\text{ft}^2}{\text{mi}^2} \times 3.557 \times 10^{-5} \text{ mi}^2/\text{ft}^2]$$

$$= 4.04 + 2.84 + 3.28$$

$$= 10.2 \text{ mi}^2$$

$$10.56 \text{ mi}^2 \text{ (by report)}$$

below Upper Promised Land Dam 3.3 mi²

" " " " " 3.99 mi²

Hydrograph Parameters (Snyder method)

$$t_p = C_t (L L_c)^{0.2}$$

$$L = 3.0 \text{ miles}$$

$$L_c = 1.2 \text{ miles}$$

$C_t = 1.23$ } supplied by COE
 $C_p = 0.45$ } Zone 1

$$t_p = 1.23 (3)(1.2)^{0.2} = 1.8 \text{ hr.}$$

$$t_r = \frac{t_p}{5.5} = \frac{1.8}{5.5} = 0.3 \text{ hr.}$$

Probable Maximum Storm (PMS) (Hydromet 33)

Zone 1 (Fig. 1)

$$\text{Probable Max. Precip. (PMP)} = 22.2 \text{ in.} \quad (200 \text{ mi}^2, 24 \text{ hr})$$

Depth - Area - Duration Relationships

$$\text{Maximum 6 hr} = 111\% \text{ PMP}$$

$$\text{Maximum 12 hr} = 123\% \text{ PMP}$$

$$\text{Maximum 24 hr} = 133\% \text{ PMP}$$

Loss Rate

$$\text{initial loss} = 1''$$

$$\text{uniform loss} = 0.05 \text{ in/hr}$$

SUBJECT	SHEET	BY	DATE	JOB NO
Lower Promised Land Dam	11	D12P	12/15/7	1841-010

Base flows

$$1.5 \text{ cfs/mi}^2 \times 3.99 \text{ mi}^2 = 6.0 \text{ cfs}$$

Elevation - Area - Capacity Data

<u>Elev.</u>	<u>Area (mi²)</u>	<u>Area (acres)</u>
1715	0.29	185.6 **
1720	0.63	403.2
1740	1.11	710.4
1707		250 *
1700	-	51 } see next page
1693		0 }

* from Inventory

** do not use conflicts with
Inventory



O'BRIEN & GERE

SUBJECT

LPLD

SHEET

12

BY

DRP

DATE

1/18/79

JOB NO

Extend Elevation-Area-Capacity Data below spillway crest
using conic method

Elev = 1707.0

A = 250 acres

 $V = 332,000,000 \text{ gal} = 47,192,513 \text{ cu ft}$

+ from rough engineers scale on file
& inventory

Top of Embankment = 1717

Base = 1693

Single cone

$$h = 1707 - 1693 = 14'$$

$$V = \pi r^2 \frac{h}{3} = \frac{Ah}{3} = 250 \text{ acres} \left(\frac{14}{3} \right) = 1167 \text{ acre-ft}$$

$$= 50,820,000 \text{ cu ft}$$

close broad into
2 cones

2 cones assume areas at $h/2$, A = area at h p = %

$$V = \frac{h/2}{3} (A + pA + \sqrt{pAA}) + \frac{h}{3} (pA)$$

$$= \frac{h/2}{3} (A + 2pA + \sqrt{pA^2})$$

$$47,192,513 \text{ cu ft} = \frac{7}{3} (250)(43,560) (1 + 2p + \sqrt{p})$$

$$1.86 = 1 + 2p + \sqrt{p}$$

$$2p + \sqrt{p} = 0.86$$

$$p = 0.2$$

$$p = 0.21$$

$$2(0.2) + (0.44) = 0.84$$

$$2(0.21) + 0.46 = 0.88$$

$$p = 0.205$$

$$A \text{ at break} = 0.205(250) = 51.3 \text{ acres}$$

check

$$V = \frac{7}{3} (250 + 102.6 + \sqrt{250(51.3)}) = 1087 \text{ acre-ft}$$

$$= 47,348,740 \text{ cu ft} \checkmark$$

good

5/13/79

Spillway Discharge Rating

$$Q = C L H^{3/2}$$

broad crested weir $B = 2.5'$
(flat upstream, slope 1 ft.
avg uping between broad
crested and triangular)

$$C = 3.2$$

Reduce L for pier & abutment effects
3 weirs, 2 at same elevation

$$L = L' - 2(NK_p + K_a)H_e$$

Center weir elev = 1707.0

2 pointed piers, no abutment, $L' = 48.5'$

$$L = 48.5 - 2(0) = 48.5'$$

<u>H (ft)</u>	<u>C</u>	<u>Q (cfs)</u>	<u>Elev.</u>	Upper chord elev \approx 1717.0 Lower chord elev \approx 1714.0
0.3	3.2 ↓ ↓ ↓ ↓ ↓ ↓	26	1707.3	
0.8		110	1707.9	
1.5		285	1708.5	
3.0		806	1710.0	
4.5		1482	1711.5	
6.0		2281	1713.0	
7.0		2874	1714.0	

SUBJECT	SHEET	BY	DATE	JOB NO
Lower Pomard Land Dam	14	DRP	12/19/78	1841-010

Rev 5/15/79

Incl weirs elev 1707.5

1 pointed pier, abutment w/ 4" approach, $L = 45.75'$

$$L = 45.75' - 2(0 + 0)H_0 = 45.75'$$

$H(A)$	C	$Q_2 (cfs)^*$	Elev
0	3.2	0	1707.5
0.3		24	1707.5
1.0		146	1708.5
2.5		579	1710.0
4.0		1171	1711.5
5.5		1888	1713.0
6.5		2426	1714.0

* values for
single weir

combined spillway Discharge Rating - Weir flow

Elev	Q_1	Q_2	$2Q_2$	$2Q_2 + Q_1 (cfs)$
1707.0	0	0	0	0
1707.3	26	0	0	26
1707.8	110	24	48	158
1708.5	235	146	292	577
1710.0	306	579	1158	1964
1711.5	1482	1171	2342	3824
1713.0	2281	1888	3776	6057
1714.0	2874	2426	4852	7726

Water surface level between 1714 and 1717

Pressure flow occurs with WSEL between 1714 & 1717

$$Q = cA\sqrt{2gH}$$

(Design of Small Dams)

$$c = 0.62$$

A = Area

H = Head on orifice

$$\text{Area (center opening)} = 48.5(7) = 339.5 \text{ ft}^2$$

$$\text{Area (end opening)} = 45.75(6.5) = 297.4 \text{ ft}^2$$

$$Q_1 = 0.62(339.5)\sqrt{2(32.2)H}$$

$$= 1389.2\sqrt{H}$$

$$Q_2 = 0.62(297.4)\sqrt{2(32.2)H}$$

$$= 1479.7\sqrt{H}$$

WSEL	Center Opening		End Openings			Total Q
	H ₁	Q ₁	H ₂	Q ₂	2Q ₂	Q ₁ + 2Q ₂
1714	3.5	3160	3.25	2668	5335	8495
1715	4.5	3583	4.25	3050	6100	9683
1716	5.5	3962	5.25	3390	6780	10742
1717	6.5	4307	6.25	3697	7395	11705

* assumes water level over orifice

Water surface level above 1717

Combination of pressure and weir flow

Weir

$$Q = CLH^{3/2}$$

broad crested weir

$$B \approx 15 \text{ ft}$$

$$C = 3.1$$

in values

See next page

SUBJECT

Lower Promised Land Dam.

SHEET

16

BY

DRP

DATE

1/2/79


JOB NO

18A1-010

5/15/79

WESEL	Pressure flow				Weir flow				Q total
	H ₁	Q ₁	H ₂	Q ₂	H _w	L _w	C	Q _w	Q ₁ + Q ₂ + Q _w
1718	7.5	4624	7.5	4051	1	280	3.1	863	13,598
1719	8.5	4905	8.5	4214	2	325	3.1	2850	16403

* assuming promised level out of pipe



**O'BRIEN & GERE**

SUBJECT

Lower Promised Land Dam

SHEET

17

BY

DRP

DATE

1/3/79

JOB NO.

1841-010

5/13/79

Combined Discharge RatingFlow.Q (cfs)

1707.0

0

1707.3

26

1707.8

158

1708.5

577

1710.0

1964

1711.5

3824

1713.0

6057

1714.0

7726

1715.0

9,683

1716.0

10,742

1717.0

11,705

1718.0

13,598

1719.0

16,408



O'BRIEN & GERE

SUBJECT

Lower Promised Land Dam

SHEET

18

BY

DRP

DATE


1/3/79

JOB NO

1541-010

Rev 5/13/79

Discharge Rating Curve
for Lower Promised Land
Dam



.....
 FLOOD HYDROGRAPH PACKAGE (MEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

1	A1	0	150	0	30	0	0	0	0	-4	0
2	A2	1	5	9	1	0.4	0.5	0.6	0.7	0.8	0.9
3	A3	0	0	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0
4	B1	0	0	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9
5	B2	0	0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8
6	B3	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
7	J1	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
8	K1	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
9	K2	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
10	K3	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
11	P	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
12	T	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
13	W	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
14	X	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
15	X	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
16	K1	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
17	Y	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
18	V1	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
19	V2	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
20	V3	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
21	V4	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
22	V5	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
23	V6	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
24	V7	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
25	V8	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
26	V9	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
27	V10	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
28	V11	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
29	V12	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
30	V13	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
31	V14	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
32	V15	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
33	V16	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
34	V17	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
35	V18	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
36	V19	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
37	V20	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
38	V21	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
39	V22	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
40	V23	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
41	V24	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
42	V25	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
43	V26	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
44	V27	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
45	V28	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
46	V29	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
47	V30	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
48	V31	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
49	V32	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
50	V33	0	0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7

NATIONAL DAM INSPECTION PROGRAM
 LOWER LAKE DAM PROMISED LAND-PA.
 PMF HYDROGRAPH

RUNOFF TO UPPER PROMISED LAND LAKE

RUNOFF THROUGH UPPER PROMISED LAND LAKE

CHANNEL ROUTING

COMBINE INFLOW AND RUNOFF HYDROGRAPHS FOR LOWER PROMISED LAND LAKE

RUNOFF THROUGH LOWER PROMISED LAND LAKE

3h.20

931707.0
40 1717
r 99

51
52
53

.....
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

RUN DATE 06/06/79.
 TIME 09.10.25.

Sh. 21

NATIONAL DAM INSPECTION PROGRAM
 LOWER LAKE DAM, PROMISED LAND, PA.
 PMF HYDROGRAPH

JOB SPECIFICATION									
NQ	NHD	NMIN	IDAY	IMR	IMIN	METRC	IPLT	IPRT	NSTAN
150	0	30	0	0	0	0	0	-4	0
		JOPER	5	NWT	LROPT	TRACE			
				0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIO= 0 LRTIO= 1

RTIOS=	.20	.30	.40	.50	.60	.70	.80	.90	1.00
--------	-----	-----	-----	-----	-----	-----	-----	-----	------

.....

SUB-AREA RUNOFF COMPUTATION

RUNOFF TO UPPER PROMISED LAND LAKE

ISTAD	ICOMP	IECON	ITAPF	JPLT	JPRT	INAME	ISTAGE	IAUTO
A1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA			
INVDG	IUNG	TAREA	SNAP
1	1	6.57	0.00

PRECIP DATA			
SPFE	PMS	R6	R12
0.00	22.20	111.00	123.00

TRSPC COMPUTED BY THE PROGRAM IS .802

LOSS DATA			
LM-DPT	STKR	DLTKR	RTIOL
0	0.00	0.00	1.00

UNIT HYDROGRAPH DATA			
TP	2.30	CP	.45
			NTA= 0

RECESSION DATA	
STRTO=	-1.50
	ORCSN= -.05

UNIT HYDROGRAPH 43 END-OF-PERIOD ORIGINATES, LAG= 2.30 HOURS, CP= .45 VOL= 1.00			
72..	267.	523.	813.
389..	340.	298.	266.
102..	89.	78.	68.
27..	23.	21.	16.
7..	6.	5.	14.
			759.
			199.
			174.
			153.
			501.
			508.
			117.
			31.
			40.
			11.
			9.
			444.

0
MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP 0 MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP 0

SUM 23.68 21.82 1.86 189142.
(401.11 554.11 47.11 5355.90)

sh.22

HYDROGRAPH ROUTING

ROUTING THROUGH UPPER PROMISED LAND LAKE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTARF	IAUTO
A2	1	0	0	0	0	1	0	0
ROUTING DATA								
OLOSS	AVG	IRIS	ISAMF	IOPT	IPMP	LSTR		
0.0	0.000	1	1	0	0	0		
NSTPS	NSTOL	LAG	AMSKK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	-1726.	-1	

STAGE	1726.10	1726.80	1727.60	1729.10	1730.60	1731.10	1732.60	1734.10	1735.60
FLOW	0.00	59.00	185.00	512.00	923.00	1074.00	2254.00	4171.00	7844.00

SURFACE AREA=

0. 287.

1216.

CAPACITY=

0. 507.

31281.

ELEVATION=

1115. 1720.

1760.

CREL	SPWID	COBW	EXPW	ELEVEL	COOL	CAREA	EXPL
1726.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA
TOPEL 1731.1
COOD 0.0
EXPD 0.0
DAMWID 0.

PEAK OUTFLOW IS	421. AT TIME	26.00 HOURS
PEAK OUTFLOW IS	684. AT TIME	26.00 HOURS
PEAK OUTFLOW IS	956. AT TIME	25.50 HOURS
PEAK OUTFLOW IS	1432. AT TIME	25.00 HOURS
PEAK OUTFLOW IS	1986. AT TIME	24.50 HOURS
PEAK OUTFLOW IS	2636. AT TIME	24.00 HOURS
PEAK OUTFLOW IS	3353. AT TIME	23.50 HOURS

PEAK OUTFLOW IS 4042. AT TIME 23.00 HOURS

PEAK OUTFLOW IS 5472. AT TIME 22.00 HOURS

5h.42

.....

.....

.....

.....

.....

.....

HYDROGRAPH ROUTING

CHANNEL ROUTING

ISTAQ	ICOMP	TECON	ITAPF	JPLT	JPPT	JNAME	ISTARE	IAUTO
A3	1	0	0	0	0	1	0	0
ROUTING DATA								
QLOSS	CLOSS	AVG	IRCS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS NSTDL LAG AMSKK X TSK STORA ISPRAT								
	1	0	0	0.000	0.000	0.000	0.000	0

NORMAL DEPTH CHANNEL ROUTING

QN(17	QN(2)	QN(3)	ELNVT	ELMAX	RLNTH	SEL
.1200	.0400	.1200	1713.7	1740.0	250.	.00300

CROSS SECTION COORDINATES--STA+ELEV, STA+ELEV--ETC
0.00 1740.00 100.00 1720.00 200.00 1714.20 201.00 1713.70 249.00 1713.70
250.00 1714.20 300.00 1720.00 450.00 1740.00

STORAGE	0.00	.45	1.17	2.18	3.47	5.03	6.75	8.60	10.60	12.73
	15.00	17.41	19.95	22.63	25.45	28.41	31.50	34.73	38.10	41.61
OUTFLOW	0.00	176.72	600.84	1261.56	2169.00	3358.19	4833.72	6563.99	8548.27	10787.75
	13284.87	16042.86	19085.51	22357.00	25921.76	29764.46	33889.89	38302.97	43008.66	48012.03
STAGE	1713.70	1715.08	1716.47	1717.85	1719.24	1720.62	1722.01	1723.39	1724.77	1726.14
	1727.54	1728.93	1730.31	1731.69	1733.08	1734.46	1735.85	1737.23	1738.62	1740.00
FLOW	0.00	176.72	600.84	1261.56	2169.00	3358.19	4833.72	6563.99	8548.27	10787.75
	13284.87	16042.86	19085.51	22357.00	25921.76	29764.46	33889.89	38302.97	43008.66	48012.03

MAXIMUM STAGE IS	1715.9
MAXIMUM STAGE IS	1716.6
MAXIMUM STAGE IS	1717.2
MAXIMUM STAGE IS	1718.1
MAXIMUM STAGE IS	1719.0
MAXIMUM STAGE IS	1719.8

5/15

.....

SUR-AREA RUNOFF COMPUTATION

RUNOFF TO LOWER PROMISED LAND LAKE

ISTAQ	ICOMP	IECON	ITYPE	JPLT	JPRY	INAMF	ISTAGE	IAUTO
RI	0	0	0	0	0	1	0	0

IHYDG	IUHG	TAREA	HYDROGRAPH DATA					TSNOV	TSAME	LOCAL
			SNAP	TRSDA	TRSPC	RATIO				
1	1	3.99	0.00	10.56	0.00	0.000	0	1	0	

	PMS	R6	PRECIP DATA			R48	R72	R96
			R12	K24				
SPFE	0.00	22.20	111.00	123.00	133.00	0.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .802

LOSS DATA						
LROPT	STRKR	DLYMR	RTTOL	ERAIN	RTIOK	STRTL
	0.00	0.00	1.00	0.00	1.00	1.00
0	0.00	0.00	1.00	0.00	1.00	1.00
						CNSTL
						ALSHX
						RTIMP
						0.00
						0.00

UNIT HYDROGRAPH DATA
TP= 1.80 CP= .45 NTA= 0

```
STPTQ= -1.50      RFCESSION DATA      RTIOR= 2.00
                ORCSV= -.05
```

UNIT HYDROGRAPH 34				END-OF-PERIOD ORIGINATES	LAG=	1.82 HOURS.	CP=	.45	VOL = 1.00
81-	296.	527.	619.	566.	478.	403.	340.	287.	242.
004.	172.	145.	123.	104.	74.	62.	52.	44.	
37.	32.	27.	22.	19.	16.	13.	11.	10.	
7.	6.	5.	4.					8.	

0		END-OF-PERIOD FLOW				PERIOD							
MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP 0	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP 0

SUM	23.68	21.42	1.86	115907.
	(601.)	(554.)	(47.)	(3282.12)

.....

COMBINE HYDROGRAPHS

COMBINE INFLOW AND RUNOFF HYDROGRAPHS FOR LOWER PROMISED LAND LAKE

ISTAQ	ICOMP	IECON.	ITAPE	JPLT	JPRY	INAME	ISTAGF	IAUTO
B2	2	0	0	0	0	1	0	0

HYDROGRAPH ROUTING

ROUTING THROUGH LOWER PROMISED LAND LAKE

ISTAO 83 ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 IASTAGE 0

QLOSS 0.0 CLOSS 0.000 AVG 0.000 IRES 1 ISAMF 1 IOPT 0 IPMP 0 LSTR 0

NSTPS 1 NSTDL 0 LAG 0 AMSKK 0 X 0.000 0.000 0.000 -1707. -1

STAGE 1707.00 1707.30 1707.80 1708.50 1710.00 1711.50 1713.00 1714.00 1715.00 1716.00

FLOW 11705.00 13598.00 158.00 577.00 1964.00 3824.00 6057.00 7726.00 9683.00 10742.00

SURFACE AREA= 0. 51. 250. 403. 710.

CAPACITY= 0. 119. 1085. 5291. 16283.

ELEVATION= 1693. 1700. 1707. 1720. 1740.

CREL 1707.0 SPMID 0.0 COQW 0.0 EXPW 0.0 ELEV 0.0 COOL 0.0 CAREA 0.0 EXPL 0.0

TOPEL 1717.0 COOD 0.0 EXPD 0.0 DAMWID 0.0

PEAK OUTFLOW IS 1097. AT TIME 21.00 HOURS

PEAK OUTFLOW IS 1740. AT TIME 21.00 HOURS

PEAK OUTFLOW IS 2458. AT TIME 21.00 HOURS

PEAK OUTFLOW IS 3189. AT TIME 20.50 HOURS

PEAK OUTFLOW IS 3945. AT TIME 21.00 HOURS

PEAK OUTFLOW IS 4846. AT TIME 21.00 HOURS

PEAK OUTFLOW IS 5786. AT TIME 21.50 HOURS

PEAK OUTFLOW IS 6837. AT TIME 21.50 HOURS

PEAK OUTFLOW IS 8254. AT TIME 22.00 HOURS

517.56

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1 .20	RATIO 2 .30	RATIO 3 .40	RATIO 4 .50	RATIO 5 .60	RATIO 6 .70	RATIO 7 .80	RATIO 8 .90	RATIO 9 1.00
HYDROGRAPH AT	A1	6.57 (17.02)	1	2386. (67.57)	3579. (101.36)	4772. (135.14)	5966. (168.93)	7154. (202.71)	8352. (236.50)	9545. (270.28)	10738. (304.07)	11931. (337.85)
	A2	6.57 (17.02)	1	421. (11.91)	684. (19.36)	956. (27.06)	1432. (40.55)	1866. (54.22)	2636. (76.65)	3353. (94.95)	4042. (114.47)	4472. (154.94)
ROUTED TO	A3	6.57 (17.02)	1	421. (11.91)	684. (19.38)	956. (27.07)	1431. (40.53)	1985. (56.10)	2637. (74.66)	3355. (94.99)	4040. (114.41)	5498. (155.67)
	B1	3.99 (10.33)	1	1667. (47.06)	2493. (70.59)	3324. (94.12)	4155. (117.65)	4986. (141.10)	5817. (164.71)	6648. (188.24)	7478. (211.77)	8309. (235.30)
2 COMBINED	H2	10.56 (27.35)	1	1788. (50.62)	2709. (76.70)	3640. (103.08)	4568. (129.35)	5509. (155.99)	6458. (182.87)	7405. (209.68)	8351. (236.47)	9487. (268.63)
	B3	10.56 (27.35)	1	1097. (31.05)	1740. (49.28)	2458. (69.61)	3189. (90.30)	3945. (111.71)	4846. (137.22)	5786. (163.83)	6837. (193.62)	8254. (233.74)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

RATIO OF PHF	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1726.30 2641. 17.	SPILLWAY CRFST 1726.10 2554. 0.	TOP OF DAM 1731.10 5048. 1074.	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS				
.20	1728.68	3765.	421.	0.00	0.00	26.00	0.00
.30	1729.73	4303.	684.	0.00	0.00	26.00	0.00
.40	1730.71	4431.	956.	0.00	0.00	25.50	0.00
.50	1731.56	5307.	1432.	46	9.50	25.00	0.00
.60	1732.26	5716.	1986.	1.16	14.50	24.50	0.00
.70	1732.90	6100.	2636.	1.80	17.00	24.00	0.00
.80	1733.46	6446.	3553.	2.36	19.00	23.50	0.00
.90	1734.00	6786.	4042.	2.90	20.50	23.00	0.00
1.00	1734.33	6996.	5472.	3.23	21.50	22.00	0.00

PLAN 1 STATION A3

RATIO	MAXIMUM FLOW-CFS	MAXIMUM STAGE-FT	TIME HOURS
.20	421.	1715.9	26.00
.30	684.	1716.6	26.00
.40	956.	1717.2	26.00
.50	1431.	1718.1	25.00
.60	1986.	1719.0	24.50
.70	2637.	1719.8	24.00
.80	3553.	1720.6	23.50
.90	4040.	1721.3	23.00
1.00	5496.	1722.5	22.50

30.27

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION
STORAGE
OUTFLOW

INITIAL VALUE
1707.30
1160.
26.

SPILLWAY CREST
1707.00
1085.
0.

TOP OF DAM
1717.00
4140.
11705.

RATIO
OF
PMF

MAXIMUM
RESERVOIR
W.S.ELEV

MAXIMUM
DEPTH
OVER DAM

MAXIMUM
STORAGE
AC-FT

MAXIMUM
OUTFLOW
CFS

DURATION
OVER TOP
HOURS

TIME OF
MAX OUTFLOW
HOURS

TIME OF
FAILURE
HOURS

27.25

.20
.30
.40
.50
.60
.70
.80
.90
1.00

1709.04
1709.76
1710.40
1710.99
1711.58
1712.19
1712.82
1713.47
1714.27

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00

1623.
1615.
1996.
2167.
2343.
2526.
2722.
2929.
3190.

1097.
1740.
2458.
3189.
3945.
4846.
5786.
6837.
8254.

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00


21.00
21.00
21.00
20.50
21.00
21.00
21.50
21.50
22.00

0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00
0.00


APPENDIX

D

Photographs



**VIEW OF THE SPILLWAY, STILLING BASIN
AND BRIDGE STRUCTURE**



**VIEW OF THE SPILLWAY AND BRIDGE
FROM THE UPSTREAM SIDE**




**THE UPSTREAM SIDE OF THE DAM SHOWING THE
SPILLWAY STRUCTURE, BRIDGE, AND THE EMBANKMENT**




**VIEW OF LOWER LAKE FROM THE
LOWER LAKE DAM BRIDGE**



**VIEW OF THE UPSTREAM SLOPE OF THE RIGHT
ABUTMENT SHOWING EROSION ALONG THE WINGWALL**



**APRON AND ENDSILL OF THE
STILLING BASIN**



**OUTLET CONDUIT
EMBEDDED IN THE ENDSILL**



**WALLENPAUPACK CREEK
DOWNSTREAM OF THE DAM**



*APRON AND ENDSILL OF
THE STILLING BASIN*

APPENDIX

E

Drawings



SUBJECT

Lowell Lake Dam

SHEET


BY






DATE

JOB NO

TABLE OF CONTENTS APPENDIX E

Regional Vicinity Map	Plate 1
Spillway Plan & Details	Plate 2
Cross-Sections	Plates 3 & 4
Plan & Sketch of Anchor Road	Plate 5
Problem Areas	Plate 6





ATION B-B
CALE 12-21-00


BENDS NOT LESS THAN 30° LR

Hand-drawn sketch of a bent pipe section. The sketch shows a horizontal line representing the pipe, with a vertical line indicating a bend. The bend is labeled "BENDS NOT LESS THAN 30° LR". Below the sketch, the dimensions are given as 4 1/2" - 5" - 4 1/2".


WATERSTOP
DETAIL
NO SCALE

[illegible]


SECTION A-A
SCALE 1/4" = 1'-0"





SECTION 1-1
SCALE 1/4" = 1'-0"



SECTION 2-2
SCALE 1/4"=1'-0"



SECTION THROUGH
WING WALL
SCALE 1/4" = 1'-0"




SECTION 3-3
SCALE 3/8"=1'-0"


Plate 2

REVISED					PROJECT NO.-G.S.A.-121-1			
	SUBMITTER:				PROMISED LAND PARK			
	ARCHITECT							
	SUBMITTER:				PINE COUNTY			
	ENGINEER				PINE COUNTY			
	APPROVED:				SPILLWAY PLAN & DETAILS			
	DEPARTMENT OF FORESTS & WATERS-BUREAU OF RECREATION							
	APPROVED:							
	ENGINEERING ENGINEER				L. ROBERT JENNELL			
	ARCHITECTURAL - ENGINEERING UNIT G.S.A.				PROJECT NO. 121-1			
CHECKED BY THE GENERAL STATE AUTHORITY				DATE				
ARCH.	STRUCT.	MECH.	PLUMB.	ELECT.	THE GENERAL STATE AUTHORITY			
					APPROVED			
					ALLANER ENGINEERING			
					SCALE			
					AS SHOWN			







1+00



1+20



1+40



1+60

- KEY**
- BACKFILL
 - CRUSHED STONE FILL
 - CONCRETE
 - RIP RAP
 - EXISTING GRADE - SOIL
 - EXISTING GRADE - ROCK
 - FINISHED GRADE OR EXCAVATION LINE
 - SELECT BACK FILL

REVISED

SUBMITTED				
ARCHITECT				
SUBMITTED				
ENGINEER				
APPROVED				
DEPARTMENT OF FORESTS & WATERS - BUREAU OF RECREATION				
APPROVED:				
SUPERVISING ENGINEER				
ARCHITECTURAL - ENGINEERING UNIT G.S.A.				
CHECKED BY THE GENERAL STATE AUTHORITY				
ARCH	STRUCT.	HEAT	PLUMB	ELECT.

Plate 3

PROJECT NO. - G.S.A. - 121 - 1

PROMISED LAND PARK






PINE COUNTY PENNSYLVANIA





CROSS SECTIONS

STATION 0+00 TO 1+60

L. ROBERT HUNNELL
CONSULTING ENGINEER

DATE	THE GENERAL STATE AUTHORITY	REVIEWED
GEORGE N. LEADER	PRESIDENT	
A. J. CARNO	EXECUTIVE ENGINEER	
HARRISON	POWER ENGINEER	








BACK FILL
CRUSHED STONE FILL
CONCRETE
RIP RAP
EXISTING GRADE SOIL
EXISTING GRADE ROCK
FINISHED GRADE OR
EXCAVATION LINE
SELECT BACK FILL

[illegible]

SUBMITTED:				
ARCHITECT				
SUBMITTED:				
ENGINEER				
APPROVED:				
DEPARTMENT OF FORESTS & WATERS - BUREAU OF RECREATION				
APPROVED:				
SUPERVISING ENGINEER				
ARCHITECTURAL - ENGINEERING UNIT G.S.A.				
CHECKED BY THE GENERAL STATE AUTHORITY				
ARCH	STRUCT	HEAT	PLUMB	ELECT

<p>Plate 4</p> <p>PROMISED NO.-G.S.A.- 121-1</p> <p>PROMISED LAND PARK</p> <p>PIKE COUNTY PENNSYLVANIA</p> <p>CROSS SECTIONS</p> <p>STATION 1+80 TO 3+40</p> <p>L. ROBERT KIMBALL CONSULTING ENGINEER</p>			
DATE	THE GENERAL STATE AUTHORITY GEORGE M. LEADER		NO. 9
SCALE 1" = 40'	A. J. CARUSO - EXECUTIVE DIRECTOR HARRISBURG PENNSYLVANIA		





PLAN

SCALE $\frac{1}{8}" = 1'-0"$

NOTE:

*9 BARS TO BE GROUTED WITH
NON-SHRINKING GROUT.

ROCK LINE

N
 $\frac{1}{4}" = 1'-0"$

OLE

Plate
PLAN
SHOWING
ANCHOR
PROJECT
L. ROBI
CONSULT




Plate 5

SKETCH

LOCATION OF

HOR. RODS.

AND LAND DAM

CT NO G.S.A. 121-1

BERT KIMBALL

ENGINEER

LOWER LAKE

←




Plate 6
Lower Lake Dam
NOT TO SCALE

APPENDIX

F

Site Geology

SITE GEOLOGY

LOWER LAKE DAM

Lower Lake Dam is situated in Pike County and within the limits of the Eastern Glaciated section of the Appalachian Plateau physiographic province. Thick deposits of glacially derived debris and till cover the nearly horizontally bedded, red, gray and green shale and sandstone units of the Devonian Catskill group of marine and continental sediments. The dam and lake both rest on glacial till and ground moraine deposits which are dense, compact and relatively impermeable. Prior to construction of the lake the area was covered with high valley swamps and bogs, attesting somewhat to the compactness and impervious nature of the dense, glacial till mantle.

No known faults or major structural defects occur in the bedrock in the vicinity of the dam and lake.

